

## NOTES:

- FOLLOW PROCEDURES NOTED IN PUB 72M, SECTIONS RC-25M AND RC-26M, INCLUDING INSTRUCTION FOR PLACING REINFORCING STEEL, TIE BOLTS, AND LOAD TRANSFER DEVICES.
  FOLLOW PROCEDURES NOTED IN PUB 408, SECTION 516 CONCRETE PAVEMENT PATCHING.
- 3. SURFACE TEXTURE AS PER PUB. 408, SECT. 501.3(K).
- 4. FOR LIMITS OF CONCRETE REPLACEMENT SEE DEPT. REG. 459, SECT. 459.8(i)(4).
- 5. CUT BACK IS NOT REQUIRED BEYOND A TRANSVERSE OR LONGITUDINAL JOINT OR CURB.
- 6. SPECIAL CONDITIONS OF OCCUPANCY PERMIT MAY SUPERCEDE THIS DETAIL.

## PENNDOT RIGID PAVEMENT RESTORATION

NOT TO SCALE

REVISED 7/20/22

P.C.A.

RIGID PAVEMENT RESTORATION PREPARED FOR: PERKASIE REGIONAL AUTHORITY

ANDERSEN ENGINEERING SSOCIATES INCORPORATED 150 RIDGE ROAD, SUITE 2, SKILERSVILLE, PA 18960

(215) 257-5711

CHK BY: P.C.A DATE: 4/04/96 DWG NO. PRA-S023

DSN BY: